

# Crittenden and Theuerkauf Electrical Upgrades

March 4, 2021



# Scope of Work

#### Scope of Work

- Crittenden Middle School
  - Installation of new main breaker in main switchboard
  - Installation of new distribution breakers in main switchboard
- Theuerkauf Elementary School
  - Installation of new 2,000-amp main switchboard at new location to move switchboard outside of building G.
  - Includes block wall enclosure with ornamental metal gate to conceal electrical equipment.
  - Splice existing feeders to new equipment.



# **Proposed Plans**

#### **Theuerkauf Elementary School Site Plan**



#### **Theuerkauf Elementary School Enlarged Site Plan**





# **Proposed Budget**

### **Schematic Design Budget**

#### Construction

Description	Quantity	Unit	Uni	it\$	Total	
Crittenden						
New Distribution Breakers	7	ea	\$	4,000	\$	28,000
New Main Breaker	1	ls	\$	10,000	\$	10,000
Test and Service Panel	1	ls	\$	2,500	\$	2,500
Repair Allowance	1	alw	\$	7,500	\$	7,500
Theuerkauf						
New 2000A Switchboard	1	ls	\$	125,000	\$	125,000
New Enclosure (Block w/ Gates 10'x15')	1	ls	\$	35,000	\$	35,000
Splice Feeders	6	ea	\$	2,500	\$	15,000
Extend Feeders	600	lf	\$	100	\$	60,000
Cut & Patch Existing Elec. Room	1	alw	\$	7,500	\$	7,500
Total Direct Cost			-		\$	290,500
Contractor General Conditions	10	%	\$	290,500	\$	29,050
Contractors Fee	10	%	\$	290,500	\$	29,050
Bonds and Insurance	2	%			\$	6,972
Anticipated Bid Amount			6		\$	355,572

#### **Project Cost**

Description	Quantity		Uı	nit Cost	Subtotal
Construction Budget	1	ls			\$ 355,572
Design Contingency	5	%			\$ 17,779
Construction Contingency	5	%			\$ 17,779
Architect Fees	1	ls			\$ 48,000
Architect Reimbursable Expenses	1.5	%			\$ 720
PG&E Fees	1	al	\$	35,000	\$ 35,000
Topographic Survey	1	ls	\$	3,500	\$ 3,500
Soils Report & Testing	1	%			\$ 3,556
CM Fees	4.5	%			\$ 16,001
DSA Inspector (Part Time)	2	mos.	\$	8,000	\$ 16,000
Testing Laboratory	1	%			\$ 1,500
Bid Advertisements	1	ls			\$ 1,500
DSA Fees	1.2	%	\$	391,129	\$ 4,694
CEQA	1	ls	\$	1,000	\$ 1,000
Legal	1	ls	\$	1,000	\$ 1,000
Estimated Project Cost					\$ 523,599



## Schedule

#### **Schedule**

rittenden Middle School and 189 days Mo neuerkauf Elementary School ectrical Updgrades		Mon 11/16/20	Thu 8/5/21		
Schematic Design	60 days	Mon 11/16/20	Fri 2/5/21		
BOT Action SD Approval	1 day	Thu 3/4/21	Thu 3/4/21		
Construction Documents	30 days	Fri 3/5/21	Thu 4/15/21		
PGE Application and Review	60 days	Fri 3/5/21	Thu 5/27/21		
Bid and Award	30 days	Fri 4/30/21	Thu 6/10/21		
Construction	40 days	Fri 6/11/21	Thu 8/5/21		



# Thoughts and Questions